

IITDh/IPS/2025-26/LPC/123
02nd Sep 2025

Invitation for Quotation

Name of the Work: UPS connection for the CLT 500+-Seater stage lights, normal lights & power distribution boards

Location: CLT 500+ seater, Indian Institute of Technology Dharwad, Permanent Campus

With reference to the aforementioned work, quotations are hereby invited for the said work. Interested vendors with experience in said works can submit their quotes (*as per Annexure-I*) on their official letterhead, duly attested, **in a sealed envelope via post / courier** to the following address:

To,
IPS Office (NE-113),
First Floor Admin Block,
Indian Institute of Technology Dharwad,
Permanent Campus, Chikmalligwad.
Dharwad-580011.

Deadline for submission: 16th September 2025 up to 1300 hours

NOTE:

- Any quotes received after 1300 hours on 16/09/2025 will not be accepted.
- Name of the Work / LPC number and Firm name should be mandatorily written on the sealed cover.
- The Quotes must be properly sealed.

Sd/-
Executive Engineer
Indian Institute of Technology Dharwad

Annexure-I					
BoQ for UPS connection for the CLT 500+-Seater stage lights, normal lights & power distribution boards.					
S.No	Description	Unit	Quantity	Rate in ₹	Amount in ₹
1	Supply and fixing of MCCB of 63A rating 4 pole 415V AC, 50Hz Rated short circuit breaking capacity 30kA, thermal magnetic release type, IP40, IS 60947-2, IEC 60947-2 & EN 60947-2	Nos	4		
2	MCCB Accessory Extended ROM	Nos	2		
3	Wiring for circuit/ submain wirin galong with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required.				
	4 X 16 sq.mm + 2 X 6 sq.mm earth wire	Metre	20		
4	Fabricating supplying and mounting MS box made outSWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 7tanks treatment with powder coated paint and finally finished with approved colour etc., complete. (Size 260 mm x 210 mm x 116mm)				
	14 SWG	cm2	4366		
5	Supply and fixing of lugs with insulation for the cable termination for 25sqmm (8Nos), 10 Sqmm (16Nos) and 6sqmm (8Nos) works as required.	1Job	1		
TOTAL					
GST					
GRAND TOTAL					

(Contractors Sign and Seal)